CSIR-IITR Report Code: SSP-378
Month of Preparation: November-2019
Total No. of Pages: 04

ASBESTOS FIBRE COUNT OF NORTH EAST ROOFING PRIVATE LIMITED, GUWAHATI ASSAM

FINAL REPORT

(Phase - II)
November, 2019



सीएसआईआर-भारतीय विषविज्ञान अनुसंधान संस्थान
CSIR-INDIAN INSTITUTE OF TOXICOLOGY RESEARCH
विषविज्ञान भवन, 31, महात्मा गाँधी मार्ग, पोस्ट बाक्स नं० 80, लखनऊ-226001, उ.प्र., भारत
VISHVIGYAN BHAWAN, 31, MAHATMA GANDHI MARG, POST BOX NO 80, LUCKNOW-226001, U.P. INDIA
Telephone: 0522-2611547/ 2621856 Fax: 2611547
E-mail : rpbd@iitrindia.org

Name and Address of the Client	:	North East Roofing Private Limited Regd. Office & Works Bonda, Narangi, Guwahati-781026, Assam, India
Reference No.	:	NERPL/QCD/2019-2020/245 dated 01-11-2019
Description and Identification of the Test	:	Asbestos fibre count on slides
Nature of samples	:	Ten microscopic glass slides of membrane filters along with details of sampling
CSIR-IITR Code No. for the Work	:	SSP-378
First Phase Study	:	07-05-2019
Second Phase study	:	20-11-2019

21/11/2019

Head,
Research Planning &
Business Development

डॉ० के० सी० खुल्बे/Dr. KC Khulbe
प्रमुख, अनुसंधान योजना एवं व्यापार विकास विभाग
Head, Research Planning & Business Development Division
सी.एस.आई.आर.–भारतीय विषविज्ञान अनुसंधान संस्थान
CSIR-Indian Institute of Toxicology Research
विषविज्ञान भवन 31,महात्मा गांधी मार्ग, लखनऊ–226001 भारत
Vishvigyan Bhawan 31, Mahatma Gandhi Marg, Lucknow-226001, India

Test Report

1. **Study Code No.** : SSP-378
2. **Date of Sample Collection/ Monitoring** : 13-09-2019 to 16-09-2019 (Samples collected by Industry)
3. **Test Required by Sponsor** : Asbestos fibre counts in ten slides
4. **Methodologies and reference standards used for testing :**

The counting of asbestos fibre was done using phase contrast and polarized optical microscope, Leica DMLV (Leica, Germany). The data were calculated following the flow rate of 1 liter/minute for a period of 60 minutes, as provided by the industry, and expressed as number of fibre in air per cubic centimeter (f/cc). Ref. Bureau of Indian Standard (IS: 11450).

5. **Date, sample received** : 07-11-2019
6. **Date, study initiated** : 11-11-2019
7. **Date, study completed** : 20-11-2019
8. **Test Results**

Slide No.	Locations	Code	Date of Sampling	Fibre count (f/cc)
1-N	Fibre Godown	SSP-378 (XI)	13/09/2019	0.053
2-N	Mill Area	SSP-378 (XII)	13/09/2019	0.049
3-N	Fibre Treatment Area	SSP-378 (XIII)	13/09/2019	0.043
4-N	Sheeting Machine Area	SSP-378 (XIV)	14/09/2019	0.034
5-N	Q C Personal	SSP-378 (XV)	14/09/2019	0.045
6-N	Laboratory	SSP-378 (XVI)	14/09/2019	0.035
7-N	Moulding Filing Area	SSP-378 (XVII)	15/09/2019	0.032
8-N	Reclamation/Filling Area	SSP-378 (XVIII)	15/09/2019	0.038
9-N	Dry/Wet Wastage Processing Area	SSP-378 (XIX)	15/09/2019	0.033
10-N	Dust Extractor (Mill)	SSP-378 (XX)	16/09/2019	0.051

9. Results

Asbestos fibre counts in 10 microscopic glass slides of membrane filters provided by North East Roofing Limited Guwahati, at 10 different locations are given in Table-1. Locations in fibre godown, mill area, fibre treatment area, Q C personal and dust extractor had close values of fibre counts i.e. 0.053 f/cc, 0.049 f/cc, 0.043 f/cc, 0.045 f/cc and 0.051 f/cc respectively. Other locations pertaining to sheeting machine area, laboratory, moulding filing area, reclamation/ filling area and dry/ wet wastage processing area showed fibre counts as 0.034 f/cc, 0.035 f/cc, 0.032 f/cc, 0.038 f/cc and 0.033 f/cc respectively.

10. Conclusions

These asbestos fibre counts are within National Safe Standard value of 0.100 f/cc.

AHKhan

(A.H. Khan)
Sr. Principal Scientist

11. Notes:

a. The above results relate only to the tests required by sponsor as indicated in item 3 (Page 3 of 4).

b. The report shall not be reproduced in fragments without the written approval of Director, CSIR-IITR, Lucknow.

c. This report shall not be used for any purpose other than environmental management related activities of the plant/ site by the sponsor.